

		Inspection and Test Plan – Stormwater Drainage		Doc ID: R11-DRA-ITP			
Client: Iluka Resources Limited				Prepared By: Simon Welsh		Date: 15/10/2024	
Project: Public Roads Upgrade				Reviewed By: Joshua Kliemnt		Date: 11/11//2024	
Construction Process: Stormwater Drainage				Approved By: Simon Jaworksi		Date: 11/11//2024	
Specifications: ETS100, 101, 102							
Structure / Component:							


Item No.	Task/Activity Description	Inspection/Test					Type	Responsibility	Checked/Verified by (initial/Date):			
		Frequency	Acceptance Criteria	Reference Documents	Inspection / Test Method	Record of conformity			TfNSW	Fulton Hogan	PV	Date
1	Preliminaries											
2	Check location of underground and above ground utilities	Per Area	<div><div>▪ Before You Dig contacted</div><div>▪ Excavation Permit is obtained</div></div>	WHSMP		Verification Checklist	IP	Site Engineer				
3	Check the type, size and class of pipes and other drainage structures to be laid Size: Class:.....	Per Delivery	Supplied items are: <div><div>▪ To correct spec, class, size and quantity</div><div>▪ Defect free, safely and securely stored</div><div>▪ Markings have been made as required</div><div>▪ Delivered 7 days after casting and concrete has reached specified 28 day strength</div></div>	R11.2		Verification Checklist	IP	Site Engineer				
4	Supply of precast concrete members subject to traffic and/ or earth pressure loading, and water containing structures with capacity greater than 25,000 Litres	Per Type	Submitted design and manufacturing documentations to the Project Verifier for precast concrete structures which subject to traffic loads and/or earth pressure and water retaining structures with a capacity in excess of 25,000 litres.	R11.2.4.1		Hold Point	HP	Site Engineer		HP		
5	Incorporation into the works any supplied, manufactured drainage product.	Per Lot	Submit a Certificate of Conformity to the Project Verifier 7 days prior to incorporating into the works	R11.2.6		Hold Point	HP	Site Engineer		HP		
6	Verify conformance of BH (bedding & haunch) materials Material Conformance Lot:....	G:1/ 50m³ PI:/100m³	Grading limits as per Table 6 in AS 3725 except that ≤12% passing 75µm & PI < 6	R11 3.1.1 R11/L Q6 8.1.1	T201 T109	NATA Test Report	TP	Site Engineer				
7	Verify conformance of SO (side & overlay) materials Material Conformance Lot:....	G:1/ 50m³ PI:/100m³	Max size 53mm, grading within limits in Table 7 of AS 3725 and PI >2 and < 12	R11 3.1.2 R11/L Q6 8.1.1	T201 T109 AS 3725	NATA Test Report	TP	Site Engineer				
8	Verify conformance of material Adjacent to Weepholes	Per Delivery	Broken stone or river gravel of max size 53mm and < 5% passing 9.5mm sieve	R11 3.2 R11/L	T201	NATA Test Report	TP	Site Engineer				

	Inspection and Test Plan – Stormwater Drainage	Doc ID: R11-DRA-ITP	
Client: Iluka Resources Limited		Prepared By: Simon Welsh	Date: 15/10/2024
Project: Public Roads Upgrade		Reviewed By: Joshua Kliemnt	Date: 11/11//2024
Construction Process: Stormwater Drainage		Approved By: Simon Jaworksi	Date: 11/11//2024
Specifications: ETS100, 101, 102			
Structure / Component:			


Item No.	Task/Activity Description	Inspection/Test					Type	Responsibility	Checked/Verified by (initial/Date):			
		Frequency	Acceptance Criteria	Reference Documents	Inspection / Test Method	Record of conformity			TfNSW	Fulton Hogan	PV	Date
9	Subsurface drainage pipes	Per Delivery	Provide certificate of compliance accompanied by NATA certified test results in accordance with TfNSW 3552 not more than 6 months old	R11.4.4.5 TfNSW 3552	T1505 T1506	Certificate of Conformity	IP	Site Engineer				
10	Inspect supplied items upon delivery	Per Delivery	Supplied items are to correct spec, class, size and undamaged Steel Reinforced Pipes as per CL3.3 & 3.4 of AS4058 Fibre Reinforced Pipe as per CL9 & 10 AS4139	QMP		Receiving Inspection Checklist	IP	Site Engineer				
11	Trenching and Excavation											
12	Construction of each drainage system	Per Lot	Set out the stormwater drainage systems as shown on the drawings in sufficient detail to identify: <ul style="list-style-type: none"> the locations, lengths and levels at outlets and inlets of pipes and box culvert structures; the locations and levels of gully pits, junction boxes, energy dissipaters, and inlet and outlet structures; the locations and levels of the ends of wing walls and headwalls; and the locations and levels of open drains. Notify PV that set out of drainage system has been completed.	R11.4.1.1		Hold Point	HP	Surveyor		HP		
			If set out is within 5 metres of an environmental sensitive area notify Environmental Manager	G36.4.12		Hold Point	HP	Surveyor			HP	

	Inspection and Test Plan – Stormwater Drainage	Doc ID: R11-DRA-ITP	
Client: Iluka Resources Limited		Prepared By: Simon Welsh	Date: 15/10/2024
Project: Public Roads Upgrade		Reviewed By: Joshua Kliemnt	Date: 11/11/2024
Construction Process: Stormwater Drainage		Approved By: Simon Jaworksi	Date: 11/11/2024
Specifications: ETS100, 101, 102			
Structure / Component:			

Item No.	Task/Activity Description	Inspection/Test					Type	Responsibility	Checked/Verified by (initial/Date):																																																																																																																																																																																																									
		Frequency	Acceptance Criteria	Reference Documents	Inspection / Test Method	Record of conformity			TfNSW	Fulton Hogan	PV	Date																																																																																																																																																																																																						
13	Excavate trench to the underside of bedding to correct width	Per Lot	<ul style="list-style-type: none"> Width and depth of pipe trench as per AS 3725 and standard drawings, refer to right table For other structures, the clear width between structure wall & face of excavation is $\geq 300\text{mm}$ or $1/3$ height of excavation face, whichever is greater Trenches $> 1.5\text{m}$ deep are either shored or benched The excavation is $\leq 50\text{mm}$ beyond the specified width and depths of the trench For pipes under embankments <ul style="list-style-type: none"> “Embankment Condition”: embankment is constructed to a height ≥ 0.7 times the external dia of the pipe above the top of the bed zone, and for a min lateral distance past the boundary of the trench of 2.5 times the external dia of the pipe “Trench Condition”: Trenches done after the construct of the embankment to the level of the underside of the Selected Material Zone 	<table border="1"> <thead> <tr> <th colspan="2">Pipe Size (mm)</th><th colspan="3">Minimum Depth (mm)</th><th colspan="6">Minimum Distance (mm)</th></tr> <tr> <th rowspan="2">Nominal Internal Diameter</th><th rowspan="2">Outside Diameter at Collar</th><th>Bed</th><th>Haunch</th><th>Side</th><th colspan="2">Single</th><th colspan="2">Multiple</th><th>Single CLSM</th><th>Multiple CLSM</th></tr> <tr> <th>x</th><th>y</th><th>z-y</th><th>lc</th><th>(Centreline separation)</th><th>lc†</th><th>(Centreline separation)</th><th>lc</th><th>lc†</th></tr> </thead> <tbody> <tr><td>375</td><td>543</td><td>100</td><td>165</td><td>110</td><td>400</td><td>700</td><td>450</td><td>1000</td><td>130</td><td>150</td></tr> <tr><td>450</td><td>647</td><td>100</td><td>195</td><td>130</td><td>400</td><td>800</td><td>450</td><td>1100</td><td>130</td><td>160</td></tr> <tr><td>525</td><td>736</td><td>100</td><td>220</td><td>145</td><td>400</td><td>800</td><td>450</td><td>1200</td><td>140</td><td>170</td></tr> <tr><td>600</td><td>831</td><td>100</td><td>250</td><td>165</td><td>400</td><td>900</td><td>500</td><td>1300</td><td>140</td><td>180</td></tr> <tr><td>675</td><td>926</td><td>100</td><td>280</td><td>185</td><td>400</td><td>900</td><td>500</td><td>1400</td><td>150</td><td>190</td></tr> <tr><td>750</td><td>1017</td><td>100</td><td>305</td><td>205</td><td>450</td><td>1000</td><td>500</td><td>1500</td><td>150</td><td>200</td></tr> <tr><td>825</td><td>1086</td><td>100</td><td>325</td><td>215</td><td>450</td><td>1000</td><td>500</td><td>1600</td><td>150</td><td>200</td></tr> <tr><td>900</td><td>1197</td><td>100</td><td>360</td><td>240</td><td>450</td><td>1100</td><td>500</td><td>1700</td><td>160</td><td>210</td></tr> <tr><td>1050</td><td>1391</td><td>100</td><td>415</td><td>280</td><td>450</td><td>1200</td><td>500</td><td>1900</td><td>160</td><td>220</td></tr> <tr><td>1200</td><td>1543</td><td>100</td><td>465</td><td>310</td><td>450</td><td>1200</td><td>550</td><td>2100</td><td>170</td><td>230</td></tr> <tr><td>1350</td><td>1708</td><td>150</td><td>510</td><td>340</td><td>450</td><td>1300</td><td>550</td><td>2300</td><td>170</td><td>240</td></tr> <tr><td>1500</td><td>1937</td><td>150</td><td>580</td><td>385</td><td>450</td><td>1500</td><td>600</td><td>2500</td><td>190</td><td>280</td></tr> <tr><td>1650</td><td>2089</td><td>150</td><td>625</td><td>420</td><td>450</td><td>1500</td><td>600</td><td>2700</td><td>190</td><td>280</td></tr> <tr><td>1800</td><td>2267</td><td>150</td><td>680</td><td>365</td><td>450</td><td>1600</td><td>600</td><td>2900</td><td>200</td><td>290</td></tr> <tr><td>2100</td><td>2360</td><td>150</td><td>710</td><td>470</td><td>450</td><td>1800</td><td>600</td><td>3200</td><td>200</td><td>290</td></tr> </tbody> </table>									Pipe Size (mm)		Minimum Depth (mm)			Minimum Distance (mm)						Nominal Internal Diameter	Outside Diameter at Collar	Bed	Haunch	Side	Single		Multiple		Single CLSM	Multiple CLSM	x	y	z-y	lc	(Centreline separation)	lc†	(Centreline separation)	lc	lc†	375	543	100	165	110	400	700	450	1000	130	150	450	647	100	195	130	400	800	450	1100	130	160	525	736	100	220	145	400	800	450	1200	140	170	600	831	100	250	165	400	900	500	1300	140	180	675	926	100	280	185	400	900	500	1400	150	190	750	1017	100	305	205	450	1000	500	1500	150	200	825	1086	100	325	215	450	1000	500	1600	150	200	900	1197	100	360	240	450	1100	500	1700	160	210	1050	1391	100	415	280	450	1200	500	1900	160	220	1200	1543	100	465	310	450	1200	550	2100	170	230	1350	1708	150	510	340	450	1300	550	2300	170	240	1500	1937	150	580	385	450	1500	600	2500	190	280	1650	2089	150	625	420	450	1500	600	2700	190	280	1800	2267	150	680	365	450	1600	600	2900	200	290	2100	2360	150	710	470	450	1800	600	3200	200	290		
Pipe Size (mm)		Minimum Depth (mm)			Minimum Distance (mm)																																																																																																																																																																																																													
Nominal Internal Diameter	Outside Diameter at Collar	Bed	Haunch	Side	Single		Multiple		Single CLSM	Multiple CLSM																																																																																																																																																																																																								
		x	y	z-y	lc	(Centreline separation)	lc†	(Centreline separation)	lc	lc†																																																																																																																																																																																																								
375	543	100	165	110	400	700	450	1000	130	150																																																																																																																																																																																																								
450	647	100	195	130	400	800	450	1100	130	160																																																																																																																																																																																																								
525	736	100	220	145	400	800	450	1200	140	170																																																																																																																																																																																																								
600	831	100	250	165	400	900	500	1300	140	180																																																																																																																																																																																																								
675	926	100	280	185	400	900	500	1400	150	190																																																																																																																																																																																																								
750	1017	100	305	205	450	1000	500	1500	150	200																																																																																																																																																																																																								
825	1086	100	325	215	450	1000	500	1600	150	200																																																																																																																																																																																																								
900	1197	100	360	240	450	1100	500	1700	160	210																																																																																																																																																																																																								
1050	1391	100	415	280	450	1200	500	1900	160	220																																																																																																																																																																																																								
1200	1543	100	465	310	450	1200	550	2100	170	230																																																																																																																																																																																																								
1350	1708	150	510	340	450	1300	550	2300	170	240																																																																																																																																																																																																								
1500	1937	150	580	385	450	1500	600	2500	190	280																																																																																																																																																																																																								
1650	2089	150	625	420	450	1500	600	2700	190	280																																																																																																																																																																																																								
1800	2267	150	680	365	450	1600	600	2900	200	290																																																																																																																																																																																																								
2100	2360	150	710	470	450	1800	600	3200	200	290																																																																																																																																																																																																								
R11.4.3 MD.R240-01		Verification Checklist	IP	Site Foreman																																																																																																																																																																																																														
14	Foundation Compaction	Q6/L	Foundation to be compacted to 95%. (Standard compaction)	R11.4.9.2 R11.4.9.3 Q6 8.1.1	T166	Test Report	TP	Site Engineer																																																																																																																																																																																																										
15	Excavation for pipe installation and other drainage structures	Per Lot	Notify the Project Verifier of the anticipated date of completion of excavation and preparation of foundations. Not later than 24 hours, but not earlier than 5 working days.	R11.4.3		Witness Point	WP	Site Engineer		WP																																																																																																																																																																																																								

	Inspection and Test Plan – Stormwater Drainage	Doc ID: R11-DRA-ITP	
Client: Iluka Resources Limited		Prepared By: Simon Welsh	Date: 15/10/2024
Project: Public Roads Upgrade		Reviewed By: Joshua Kliemnt	Date: 11/11/2024
Construction Process: Stormwater Drainage		Approved By: Simon Jaworksi	Date: 11/11/2024
Specifications: ETS100, 101, 102			
Structure / Component:			

Item No.	Task/Activity Description	Inspection/Test					Type	Responsibility	Checked/Verified by (initial/Date):			
		Frequency	Acceptance Criteria	Reference Documents	Inspection / Test Method	Record of conformity			TfNSW	Fulton Hogan	PV	Date
			GDR to provide Geo-report to state that the foundation is suitable or need further treatment									
16	Remove & replace unsuitable materials, if directed by PV	Where required Q6/L	Replace with materials from cuttings or conforming material to full depth in 150mm layers and compact to 95% Standard Compaction	R11.4.3 Q6 8.1.1	T166	Test Report	TP	Site Engineer				
17	Replacement of inadequate foundation material.	Where required	Notification to the Project Verifier that inadequate foundation material has been excavated to the extent required.	R11.4.3.3		Witness Point	WP	Site Engineer		WP		
18	Placement of Pipes											
19	Place Bedding	Q6/L	<ul style="list-style-type: none"> Bedding placed to a thickness of 100mm for pipes up to 1200mm dia pipes and 150mm for pipes greater than 120mm Bedding compacted to 95% 	R11 R240-01		Verification Checklist	IP	Site Engineer				
20	Install pipes in accordance to manufacturer's instructions and design documentations	Per Lot	<ul style="list-style-type: none"> Correct size and class of pipe installed Pipes laid from inlet to outlet with socket laid upstream Pipe support are Type HS3 conforming to AS3725 and MD R240-01 Pipe ends cleaned and rubber rings correctly installed Where grade exceed 20%: anchor blocks provided at 3m spacing max., at bends, junctions and where shown on drawings 100mm dia Subsurface drainage installed at the discharge end of pipes 3m long, laid beside & 100mm above invert level of drainage pipe All joints have rubber rings fitted and pipes butting against each other. Connection to pits in accordance with MD R220-43 	R11.4.4 R240-01 R220-43		Verification Checklist	IP	Site Engineer				

	Inspection and Test Plan – Stormwater Drainage	Doc ID: R11-DRA-ITP	
Client: Iluka Resources Limited		Prepared By: Simon Welsh	Date: 15/10/2024
Project: Public Roads Upgrade		Reviewed By: Joshua Kliemnt	Date: 11/11//2024
Construction Process: Stormwater Drainage		Approved By: Simon Jaworksi	Date: 11/11//2024
Specifications: ETS100, 101, 102			
Structure / Component:			

Item No.	Task/Activity Description	Inspection/Test					Type	Responsibility	Checked/Verified by (initial/Date):			
		Frequency	Acceptance Criteria	Reference Documents	Inspection / Test Method	Record of conformity			TfNSW	Fulton Hogan	PV	Date
21	Pit/headwall to pipe connection	Per connection	<ul style="list-style-type: none"> Pit to pipe connections are to be flush along the pit wall, with minimal protrusions or depressions. 	CMS 7.8		Verification Checklist	IP	Site Engineer				
22	Verify that completed pipeline against survey marks	<ul style="list-style-type: none"> Per Lot 	<ul style="list-style-type: none"> Completed pipeline is inline and within ±200mm of location (plan) Invert level are within 20mm of the design level at any point To be checked at each pit and headwall 	R11.5.1 Table R11.4		Survey Report	SC	Surveyor				
23	Construction of Drainage Structures (Other Than Pipes and Box Culverts)											
24	Construction of drainage structures other than pipes and box culverts.	Per Structure	The notification is to be at least 7 days prior to the date of installation work.	R11.4.7.2		Witness Point	WP	Site Engineer		WP		
25	Place bedding layer underneath pit, or plain concrete blinding to headwalls. Ensure correct survey tools have been used to transfer levels, i.e. dumpy level	Per Structure	The bedding materials consists either of: For Precast Pits 50mm layer DGB20 or CLSM; For other than precast a 50mm blinding layer	R11.4.7.2		Verification Checklist	IP	Site Foreman				
26	Install precast drainage structures as specified on design documentations	Per Structure	<ul style="list-style-type: none"> Installed within 14days after installation of associated pipes, box culverts or open drains Where drainage structure abuts a structure or concrete pavement, a 10mm wide filler complying with TfNSW 3204 is installed as an isolation joint Subsoil drainage pipe connected to downstream headwalls/pits Lifting holes are sealed Structure is level and plumb 	R11.4.7		Verification Checklist	IP	Site Foreman				

Client: Iluka Resources Limited

Prepared By: Simon Welsh

Date: 15/10/2024

Project: Public Roads Upgrade

Reviewed By: Joshua Kliemnt

Date:
11/11/2024

Construction Process: Stormwater Drainage


Approved By: Simon Jaworksi

Date:
11/11/2024

Specifications: ETS100, 101, 102

Structure / Component:

Item No.	Task/Activity Description	Inspection/Test					Type	Responsibility	Checked/Verified by (initial/Date):			
		Frequency	Acceptance Criteria	Reference Documents	Inspection / Test Method	Record of conformity			TfNSW	Fulton Hogan	PV	Date
27	Install Cast In place drainage structures (incl. headwalls and curtain walls) as shown on design documentations R53-GCW Lot No:	Per Structure	<ul style="list-style-type: none"> Constructed as per R53-GCW-ITP Backfilled after 14 days of placing the concrete or when the 28 day compressive strength is achieved, whichever achieved earlier Insitu curtain walls at the outer edge of the aprons are only for pipes between 300-1200mm diameter 	R11.4.7 R11.4.7.3		R53-GCW Lots	IP	Site Foreman				
28	Verify that the finished drainage structures are within tolerance, check pipe gaps over joints are within allowance	Per Structure	<ul style="list-style-type: none"> Within ± 200 mm longitudinally Within ± 20mm laterally Within ± 20mm of design invert level 	R11.5 Table R11.4		Survey Report	SU	Site Engineer				
29	Install rung ladders if pits are > 600mm deep	Per Pit	<ul style="list-style-type: none"> Top of uppermost rung < 600mm below the top of the pit. Top of Bottom Rung is within 300 to 500mm above the invert of the pit. Rung spacing is 300\pm50mm 	R11.4.7.4		Verification Checklist	IP	Site Engineer				
30	Patch grout around pipes recesses as required	Per Structure	<ul style="list-style-type: none"> Cementitious grout is placed evenly covering the entire recess of the pipe-pit connections if any 	DRA-CMS		Verification Checklist	IP	Site Foreman				
31	Install weepholes in headwalls and wingwalls, if provided	Per Structure	<ul style="list-style-type: none"> Material placed to height ≥ 450mm above the bottom of the weephole over a plan area ≥ 600mm along the wall by 300mm out from the wall (Located centrally of the weephole) Enclosed it with geotextile filter fabric 	R11.4.8 R63		Verification Checklist	IP	Site Foreman				
32	Place scour protection / dissipator, if required	Per Outlet Structure	<ul style="list-style-type: none"> Scour protection and installation of dissipater completed as details specified in design documentations 	Design DWGS		Verification Checklist	IP	Site Foreman				
33	Backfilling											
34	Place and spread haunch, side zone, overlay and backfill, compact and test to specified densities	Per Lot Q6/L	<ul style="list-style-type: none"> Backfill placed in 150mm layers and compact to 95% std compaction (102% if within SMZ) Testing frequency refer to Q6/L3.1 (every layer if within SMZ) If stabilised sand used, the materials been vibrated to obtain complete placement & compaction of 	R11.4.9.1 TfNSW Q6 Annexure Q/L Q6 8.1.1	T166 T120 T147	Test Report	TP	Site Engineer				

	Inspection and Test Plan – Stormwater Drainage	Doc ID: R11-DRA-ITP	
Client: Iluka Resources Limited		Prepared By: Simon Welsh	Date: 15/10/2024
Project: Public Roads Upgrade		Reviewed By: Joshua Kliemnt	Date: 11/11//2024
Construction Process: Stormwater Drainage		Approved By: Simon Jaworksi	Date: 11/11//2024
Specifications: ETS100, 101, 102			
Structure / Component:			

Item No.	Task/Activity Description	Inspection/Test					Type	Responsibility	Checked/Verified by (initial/Date):			
		Frequency	Acceptance Criteria	Reference Documents	Inspection / Test Method	Record of conformity			TfNSW	Fulton Hogan	PV	Date
			material under & around pipe and the placed stabilised materials are firm a day after placement. Working time to be noted. <ul style="list-style-type: none">Stabilised sand not exempt from T166 in accordance with R11Working times of stabilised sand should be considered (T147)									
35	CCTV Inspection	Per Line	<ul style="list-style-type: none">CCTV inspection of installed drainage completed after backfill of drainage line but before placement of pavementsVideo footage and report in accordance with WSA05-2008	R11.5.2		CCTV Report	IP	Site Engineer				
36	Moving heavy construction plant or vehicles over pipe or box culvert structures.	Per Location	Provide a certificate and verification of protective measures.	R11.4.11		Hold Point	HP	Site Engineer		HP		
37	Covering up of work subject to a conformity verification survey.	Per Lot	Survey Report verifying conformity.	G71.5.6.6	Survey	Hold Point	SU	Surveyor		HP		

Legend:

HP	Hold Point	Work shall not proceed past the HP until released by the Project Verifier	IP	Inspection point	Formal Inspection to be done and recorded
HP*	FH Hold Point	Work shall not proceed past the HP* until released by Fulton Hogan	TP	Test Point	Product compliance test to be undertaken and recorded/reported
WP	Witness Point	An inspection which must be witnessed by the Project Verifier	SU	Survey conformance point	A qualified surveyor to check product/section/structure and report
AP	Approval Point	Written or verbal approval given by the Project Verifier	SC	Survey Check	

Notes
