		T											
NZ TRANSPORT AGENCY  Client's Rep. : Engineers Rep Name		Downer			Start RP			INSPECTION AND TEST PLAN - VERSION CONTROL			1	2	3
				[1	Finish RP		Prepared by Project Engineer:		PE name	dd/mm/yy		1	
				Danie et Manner Timer to Maiores De	December (TIMPAD) Manks	Reviewed by Construction Manager:		PM name	dd/mm/yy		1		
				Project Name: Tirau to Waiouru Rehabilitation Acceleration Programe (TWRAP) Works			Reviewed by Surf./ Pavmt Manager:		Surfacing or Pavement Manager	dd/mm/yy		1	
		Contractor's Rep. : Contractor's Rep Name		Specifications: NZTA M23, NZTA B/2,			Approved Quality Manager.:		Nominated by Group Quality Manager	dd/mm/yy			
				Wire Rope Safety Barrier			Approved Pavements SME.:		Responsible Group SME	dd/mm/yy			
							Issued by: Project Eng		PE name	dd/mm/yy			
	Task/Activity/Description	Inspection/Test					, i			,,	Check	ked by	
Item										R = Responsible, I, Informed, A = Approve			
			Action	<u> </u>		Acceptance Criteria		Record documents (QCP - Quality Responsibility Control Portal	Project Specific Notes / Instructions			conica, A - App	1
		Detail of Activity / Test	(Hold, Monitor, Witness)	Minimum Test Frequency (Lot = 1 day's production or 1,500m2)	Inspection / Test method					Sire Engineer	Eng. Rep / NZTA	Contracto	Date
1.0. GUARDRAIL HARDWARE ACCEPTANCE													
2.0. 00/1	ADIDALE TIMES TO THE PROCEST TARGE			1			Data Charat /						
1.01	Guardrail Hardware	MASH Tested	H	1 Test per material per source	Visual / Photo	AS/NZS3845	Data Sheet / Delivery docket	Contractor		Α	I	R	dd/mm/yy
1.02	Labelling	All components labelled with AS/NZS3845	Н	1 Test per material per source	Visual / Photo	AS/NZS3845	Product/ supplier certification	Contractor		Α	1	R	dd/mm/yy
2.0. CON	ISTRUCTION												
						1	<u> </u>						
2.01	Leading and trailing treatments	Start and End locations marked out	W	All barrier lengths	Visual	Positions in agreed marked out location	Check sheet	Contractor	Note: Terminal excavation measured for acceptance against supplier diagram, Anchor bracket installed as per supplier specification and Concrete poured and screened flush or slightly proud of seal.	А	1	R	dd/mm/yy
2.02		Correct type	W	All barrier lengths	Visual	Types as specified on drawings	Check sheet	Contractor		Α	I	R	dd/mm/yy
2.03	Excavate WRSB Post Holes	Excavate post holes to a depth as specified in the design drawing	М	Where every post will be installed	Measure	Site Engineers Approval	Photo / Measurement Sheet	Contractor	Sides of excavation shall be parallel and not collapsing	A	1	R	dd/mm/yy
2.04	Cast concrete into WRSB pile	Check condition of finished pile	М	All piles	Visual / Photo	Top of pile is level and Flush with ground at front face of pile	As per manufacturer's checklist	Contractor		А	1	R	dd/mm/yy
2.05	Install WRSB	Install MashFlex post at a depth specified in the design drawing and above finished road level	Н	Where every post will be installed	Visual / Photo	Site Engineers Approval	As per manufacturer's checklist	Contractor		I	А	R	dd/mm/yy
2.06		Cables at correct position as per manufacturer's installation manual	М	All post	Visual / Photo	Cables are in or on the seating position	As per manufacturer's checklist	Contractor		A	l	R	dd/mm/yy
2.07		Ensure posts have plastic cap inserted into the post and insert MashFlex Plug into hole on side of cap.	М	All post	Visual / Photo	100%	As per manufacturer's checklist	Contractor		A	1	R	dd/mm/yy
2.08		All cables are tensioned correctly	М	All barrier lengths	Visual / Photo	As per manufacturer's installation manual	Photo	Contractor		Α	I	R	dd/mm/yy
	<u> </u>												
	<u> </u>												
									As per manufacturer's checklist				
		-		, ,		,			,				-
Client Final Inspection - the signature below verifies that this ITP has been completed in accordance with the Specifications and verifies lot compliance.							Н	Hold Point	Work Shall not proceed past the HP until r by the Eng. Rep.	eleased			

Date: \_\_\_\_\_

Signature:\_\_\_\_\_

Signature:\_\_\_\_\_

Witness Point

Monitor Point

An Inspection which must be witnessed

by the Eng. Rep.

Intermittent monitoring of any stage of the work in progress by the Eng. Rep.

Contractor's Rep Name:\_\_\_\_\_

Engineer's Rep. Name:\_\_\_\_\_