



Inspection & Test Plan

Project no.: _____ Project name: _____

Inspection Legend: H = Hold point; S = Surveillance; W = Witness

Client: _____ Water Authority: _____

Responsibility Legend: PM = Project Manager; SS = Site Supervisor; C = Client Rep; I = Inspector

No.	Inspection Activity	Specification / Drawing Reference	Inspection Procedure and Acceptance Criteria	Verification Document	Aquatec			Skerman Civil			Urban Utilities			Records / Comments
					Insp.	Resp.	Sign and date	Insp.	Resp.	Sign and date	Insp.	Resp.	Sign and date	
1.0	SITE PRELIMINARIES													
1.1	Management Plans		<input type="checkbox"/> Management Plans Submitted and approved		H	PM		H	C		H	I		
1.2	Permit to Work		<input type="checkbox"/> All required permits received		H	PM		H	C		H	I		
1.3	Drawings	Aquatec Civil/Mech Drawings	<input type="checkbox"/> IFC Drawings confirmed latest revision and approved	IFC Drawings	H	PM		H	C		H	I		
1.4	Backfill Design Approval	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Foundation and Backfill design has been reviewed and modified where necessary with letter of endorsement from RPEQ Geotech (Must be site-specific)	RPEQ Letter of Endorsement	H	PM		H	C					
1.5	Backfill Materials Approval	Aquatec Civil/Mech Drawings	<input type="checkbox"/> All backfill material certificates submitted and approved for use by Geotechnical Engineer	Material Certificates	H	PM		W	C					
2	PRECAST CONCRETE INSTALLATION													
2.1	Excavation set-out	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Setout points established and offset for recovery		W	SS		W	C					
2.2	Excavation to Base R.L.	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Shoring and benching completed as required <input type="checkbox"/> Where over-excavation occurs, excavation shall be filled with suitable material to satisfaction of geotechnical engineer		W	SS		H	C		W	I		
2.3	Testing of Base	Aquatec Civil/Mech Drawings	<input type="checkbox"/> 2 x DCP tests completed on excavation floor and bearing capacity of >100kPa confirmed <input type="checkbox"/> If excavation base material deemed unsuitable, unsuitable foundation to be replaced with suitable material with approval.	DCP Report	H	SS		H	C		W	I		
2.4	Sub-Base Preparation	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Approved Sub-Base material placed and compacted <input type="checkbox"/> Sump and pump set up to keep excavation dry (if required) <input type="checkbox"/> Pump Station Base R.L., centre and orientation set out and confirmed		W	SS		W	C		W	I		
2.5	Testing of Sub-Base	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Sub-base confirmed at 98% compaction	Compaction Test Report	H	SS		H	C		W	I		
2.6	Precast Items Check	Aquatec Coring Drawings	<input type="checkbox"/> Precast items checked for damage <input type="checkbox"/> Precast items checked against drawings for correct dimensions, cast-ins, coatings and penetrations		S	SS		W	CS		W	I		
2.7	Base and Increment Placement	Craning and Excavation Plan Aquatec Civil/Mech Drawings	<input type="checkbox"/> Precast items lifted into chamber as per craning and excavation plan <input type="checkbox"/> Precast items jointed as per drawings <input type="checkbox"/> Orientation of inlet stub and penetrations as per drawings		S	SS		W	CS		W	I		
2.8	Cover Slab Installation	Craning and Excavation Plan Aquatec Civil/Mech Drawings	<input type="checkbox"/> Cover Slab lifted onto pump station as per craning and excavation plan <input type="checkbox"/> Cover Slab orientation and alignment correct as per drawings <input type="checkbox"/> Cover Slab sealed to pump station as per drawings		S	SS		W	CS					
2.9	Placement of Ballast Concrete	Aquatec Civil/Mech Drawings	<input type="checkbox"/> 25MPa Concrete Used <input type="checkbox"/> Correct Volume Used <input type="checkbox"/> Sufficient Vibration	Concrete Dockets	S	SS		W	CS					
2.10	Placement and Compaction of Backfill	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Backfill placed and compacted in 200mm layers to 95% as per drawings <input type="checkbox"/> Compaction test taken every 5th layer (1m)	Compaction Test Reports	S	SS		W	CS					
2.11	As Built Pickup	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Survey pickup completed <input type="checkbox"/> All as-constructed data recorded.	Survey Pickups Redlined Drawings	S	SS		W	C					
3.0	PUMP STATION MECH FITOUT													
3.1	Materials check	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Pumps, Pipework, valves, fittings, fasteners, brackets, etc. as per drawings and specifications <input type="checkbox"/> Materials checked for damage	Delivery Dockets Material Certificates	H	SS		W	C					
3.2	Pump and Pipeline set out	Aquatec Pipework Layout Drawings	<input type="checkbox"/> Layouts and IL's are consistent with drawings		S	SS		W	C					

3.3	Pump Pedestal Installation	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Anchors installed to correct depth and as per manufacturers recommendation <input type="checkbox"/> Pumps level <input type="checkbox"/> Pedestal anchors torqued <input type="checkbox"/> Guide rails installed and plumb		S	SS		W	C		W	I		
3.4	Pipe and Pipe Support Installation	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Pipe and fittings installed as per project drawings <input type="checkbox"/> Pipe supports erected as per drawings with neoprene gaskets between metal and PE liner <input type="checkbox"/> Fasteners torqued correctly and marked <input type="checkbox"/> Dissimilar metals isolated <input type="checkbox"/> Pipework flushed, drained and dried as required <input type="checkbox"/> HDPE Vactor pipe vacuum tested to confirm no leaks <input type="checkbox"/> PE Welding spark testing		S	SS		W	C					
3.5	Valve Installation	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Valves installed as per drawings <input type="checkbox"/> Handles fitted and secure <input type="checkbox"/> Valve operation checked <input type="checkbox"/> Valve orientation correct <input type="checkbox"/> Fasteners torqued correctly and marked		S	SS		W	C					
3.6	Ladders and misc. installation	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Anchors installed to correct depth and as per manufacturers recommendation <input type="checkbox"/> Ladders and misc. steelwork plumb and level <input type="checkbox"/> Bracket anchors torqued with neoprene gaskets between metal and PE liner		S	SS		W	C					
3.7	Grouting	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Confirm grout product has not passed expiry date <input type="checkbox"/> Concrete surfaces scabbled as required <input type="checkbox"/> All penetrations and pipe supports grouted as per manufactures specification		S	SS		W	C					
3.8	Thrust Blocks	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Reinforcing placed as per drawings <input type="checkbox"/> 2 x layers hydrotite used <input type="checkbox"/> Walls scabbled <input type="checkbox"/> Adequate Vibration used	Concrete Dockets	H	SS		H	C		H	I		
3.9	Trench Fill and Compaction	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Marker tape installed as required <input type="checkbox"/> Trench backfilled with imported suitable trench fill		S	SS		W	C					
3.10	As Built Pickup	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Final inspection of mechanical works completed <input type="checkbox"/> Survey pickup completed <input type="checkbox"/> All as-constructed data recorded.	Survey Pickups Redlined Drawings	H	SS		H	C		H	I		
4.0	DRAINS, CONDUITS & VENTS													
4.1	Materials check	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Pipework, fittings and adhesives as per drawings		H	SS		W	C					
4.2	Pipeline set out	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Layouts and IL's are consistent with drawings		W	SS		W	C					
4.3	Pipework Connections	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Pipework installed as per project drawings <input type="checkbox"/> Invert, grade and alignment checked <input type="checkbox"/> Connections completed with no excessive loading exerted onto cast-ins.		S	SS		W	C					
4.4	Trench Fill and Compaction	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Marker tape installed as required <input type="checkbox"/> Trench backfilled with imported suitable trench fill		W	SS		W	C					
4.5	As Built Pickup	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Survey pickup completed <input type="checkbox"/> All as-constructed data recorded.	Survey Pickups Redlined Drawings	S	SS		W	C					
5.0	PUMP STATION CONCRETE SLABS													
5.1	Slab set-out	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Setout points established and offset for recovery					W	C					
5.2	Excavation for slab	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Bearing Capacity confirmed as per drawings <input type="checkbox"/> If excavation base material deemed unsuitable, unsuitable foundation to be replaced with suitable material with approval. <input type="checkbox"/> Where over-excavation occurs, excavation shall be filled with material to satisfaction of geotechnical engineer					W	C					
5.3	Formwork	Aquatec Civil/Mech Drawings	<input type="checkbox"/> Formwork installed as per drawings <input type="checkbox"/> Form release applied as required					W	C					
5.4	Reinforcement	Consultant Drawings MW Specifications	<input type="checkbox"/> Correct reinforcing sizes and spacing <input type="checkbox"/> Minimum cover as per drawing <input type="checkbox"/> Appropriate lap / cog lengths <input type="checkbox"/> Cover to conduits as per drawings					W	C					

5.6	Pre-Pour	Consultant Drawings MW Specifications	<input type="checkbox"/> Relevant persons notified of pour <input type="checkbox"/> Inspection and certification completed (as applicable) <input type="checkbox"/> all debris removed from formwork <input type="checkbox"/> Correct bar chairs and qty in place <input type="checkbox"/> Conduits positioned correctly		W	SS		H	C		H	I		
5.7	Concrete Pours	Consultant Drawings MW Specifications	<input type="checkbox"/> Concrete docket checked to confirm mix is as per drawings <input type="checkbox"/> Free dropping not permitted <input type="checkbox"/> Adequate vibration used <input type="checkbox"/> Finish as per specification and drawings	Pour record /Docket				S	C					
5.8	Post-Pour	MW Specifications AS 3600	<input type="checkbox"/> Compressive strength adequate prior to stripping <input type="checkbox"/> Curing agent applied immediately after stripping					W	C					
5.9	As Built Pickup	MW Specifications	<input type="checkbox"/> Survey pickup completed as required <input type="checkbox"/> All as-constructed data recorded.	Survey Pickups Redlined Drawings	W	SS		W	C					
6.0	ELECTRICAL INSTALLATION													
6.1	Switchboard check	Electrical Drawings	<input type="checkbox"/> Switchboard and instruments as per drawings and specifications <input type="checkbox"/> Materials checked for damage	Delivery Dockets Material Certificates	H	PM		H	C		H	I		
6.2	Switchboard check	Electrical Drawings	<input type="checkbox"/> FAT test results received	FAT Results	H	PM		H	C		H	I		
6.3	Switchboard Installation	Aquatec Civil/Mech Drawings AS 3000	<input type="checkbox"/> Conduits are installed as per drawings <input type="checkbox"/> Communications GeoSCADA <input type="checkbox"/> Mastic sealant used on underside of switchboard <input type="checkbox"/> Switchboard fixed down using correct dyna bolts		S	SS		S	C					
6.4	Switchboard Installation	Aquatec Civil/Mech Drawings AS 3000	<input type="checkbox"/> Pre SAT		S	SS		S	C		H	I		
6.5	Switchboard Installation	Aquatec Civil/Mech Drawings AS 3000	<input type="checkbox"/> SAT		S	SS		S	C		H	I		
6.6	Earthing	Electrical Drawings AS 3000	<input type="checkbox"/> Main earth stake correctly installed and labelled <input type="checkbox"/> Earthing cables terminated safely and correctly		S	SS		S	C					
6.7	Consumer Mains	Electrical Drawings AS 3000	<input type="checkbox"/> Conduits meet AS 3000 requirements and are free of obstructions <input type="checkbox"/> Conduit penetration into POS is sealed and at correct depth <input type="checkbox"/> Consumer mains installed to conduits and labelled as required <input type="checkbox"/> Cable testing and terminations completed <input type="checkbox"/> Sealing of conduits completed		S	SS		S	C					
6.8	Instrumentation and Control	Electrical Drawings AS 3000	<input type="checkbox"/> Flowmeter installed, labelled and terminated as per drawings <input type="checkbox"/> Level control instrumentation installed, terminated and labelled as per drawings <input type="checkbox"/> Pump controllers terminated and labelled as per drawings <input type="checkbox"/> Sealing of conduits completed		S	SS		S	C					
6.9	Lighting and power	Aquatec Drawings Electrical Drawings AS 3000	<input type="checkbox"/> Lighting setout as per drawings <input type="checkbox"/> Light & Power components are as per drawings		S	SS		S	C					
7.0	As Built Pickup		<input type="checkbox"/> All as-constructed data recorded.	Redlined Drawings	S	SS		W	C					
8.0	CLOSEOUT													
8.1	Non Conformances		<input type="checkbox"/> Non-conformances closed out		H	PM		H	C		H	I		
8.2	Hydrostatic Testing	AS3735	<input type="checkbox"/> AQT Test Record Documentation		H	PM		H	C		H	I		
8.3	Final Site Inspection	Project Specifications and Drawings	<input type="checkbox"/> Site Clean and Clear of all Construction Waste and Debris disposed of legally and in accordance with legislation <input type="checkbox"/> 100% Visual Inspection of install by PM, Client and MW <input type="checkbox"/> Installation checked against drawings to confirm all works are as per design <input type="checkbox"/> Site Reinstated to a standard equal to or better than existing in accordance with Project specification		H	PM		H	C		H	I		
Project Completed Date.....														

Signed By Aquatec Representative

..... Date.....

Signed By Civil Contractor Representative

..... Date.....

Signed By Water Authority Representative

..... Date.....