

| Item  | Task/Activity/Description                             | Detail of Activity   | Inspector/Test                   |   | Acceptance Criteria  | Record documents  | Responsibility                          | Comments   | Checked by               |                |            |
|---|---|--|----------------------------------|---|--|---|---|--|--------------------------|----------------|------------|
|   |   |  | Action (Hold, Monitor, Withdraw) | Minimum Test Frequency (i.e. = 1 day's production or 1,500m2)                   |  |   |   |  | Inspection / Test method | Engineer's Rep | Contractor |
| 1.1. AGGREGATE AND BINDER OPTIMISATION / ACCEPTANCE TESTING |   |  |                                  |   |  |   |   |  |                          |                |            |
| M4 AP40 Basecourse Aggregates used for overlay              |   |  |                                  |   |  |   |   |  |                          |                |            |
| 1.1.1   |   | Quality of Fines, either PI or SE or CI  | H / M*                           | 1 per 1,000 m2  | NZS4407:3.4 - PI<br>NZS4407:3.5 - CI<br>NZS4407:3.6 - SE<br>PI ≤ 5<br>CI ≤ 3<br>SE ≥ 40          | IANZ Report   | Contractor                              |  |                          |                |            |
| 1.1.2   | Notes:  | Broken Faces Content   | H / M*                           | 1 per 1,000 m2  | NZS4407:3.14<br>≥ 70% more than two broken faces on aggregates between 37.5mm and 4.75mm         | IANZ Report   | Contractor                              |  |                          |                |            |
| 1.1.3   | H = Hold point up to approval of Optimisation Testing | Particle Size Distribution   | H / M*                           | 1 per 1,000 m2  | Check if 50:50 blend of average existing (from TP9) and NZTA M/4 AP40 will meet the FBS grading. | Report using IANZ Reports for AP40 and TP PSDs  | Contractor to provide analysis          | Designer to advise if "average" blend is acceptable. |                          |                |            |
| 1.1.4   | Optimisation of Stabilizing Agent                     | Indirect Tensile Strength, ITS   | H                                | 1 Optimisation test per aggregate type  | Dry ITS: 175kPa to 400 kPa<br>Soaked ITS: 150 kPa to 350 kPa<br>TSR ≥ 70%                        | IANZ Report   | Contractor                              |  |                          |                |            |
| 1.1.5   |   | Modified Maximum Dry Density   | M                                | At Optimised Binder selection   | NZS 4402.4.1.3<br>To determine target density  | IANZ Report   | Contractor                              | Required before Stabilisation commences              |                          |                |            |
| 1.2. BEFORE STABILISATION COMMENCES                         |   |  |                                  |   |  |   |   |  |                          |                |            |
| 1.2.1   | Setout section  | Install offset pegs; record centreline, edge line or mark out stabilisation extents from existing line marking | M                                | Prior to each section   | Survey   | Document existing furniture   | Electronic survey files                 | Contractor   |                          |                |            |
| 1.2.2   | Production Plan                                       | Plan showing cut lines and sequencing of works   | M                                | Prior to each section   | Daily Report   | Points covered in NZTA B/5  | Daily Production Plan                   | Contractor   |                          |                |            |
| 1.2.3   | Weather conditions                                    | Ambient Temperature (C&I)<br>Material to be stabilised (BE&FBS)  | M                                | Prior to spreading  | Measurement  | Ambient Temperatures:<br>Cement: > 5°C, Lime: > 10°C<br>Material after stabilisation:<br>BE: > 20°C, FB: > 20°C | Daily work Log                          | Contractor   |                          |                |            |
| 1.2.4   | Weather conditions                                    | Wind   | M                                | Prior to spreading cement or lime   | Local weather stations   | Wind speed < 25 km/hr   | Daily work Log                          | Contractor   |                          |                |            |
| 1.2.5   | Weather conditions                                    | Rain   | M                                | Prior to spreading cement or lime   | Local weather stations   | No spreading of cement / lime if it is raining or likely to rain before these can be mixed in with the material | Daily work Log                          | Contractor   |                          |                |            |
| 1.3. STABILISATION OPERATION                                |   |  |                                  |   |  |   |   |  |                          |                |            |
| 1.3.1   | Stabilizing Agent                                     | Cement, GP   | M                                | Per Batch   | NZS 3122   | Conform to Specification  | Certificate in contractor's site folder | Contractor   |                          |                |            |
| 1.3.2   | Spreading of powdered stabilising agent (Cement)      | Place 1m2 canvas or 0.5m x 0.5m trays along spreader run   | M                                | every 400 m2<br>every 150m for a 2.4m width                                     | Weight mat or tray   | ± 5% of specified rate  | Daily work Log                          | Contractor   |                          |                |            |
| 1.3.3   |   | Compare area spread with weight used for each spreader load  | M                                | On-going measurement by computer/load cells                                     | Measurement each run   | ± 2.5% of specified rate  | Daily work Log                          | Contractor   |                          |                |            |
| 1.3.4   | Injection & Mixing of Water                           | In-situ Stabilisation process  | M                                | On-going visual assessment  | Visual and hand squeeze test   | Mixed material free of pockets or streaks.<br>Overlaps minimum of 150mm   | Daily work Log                          | Contractor   |                          |                |            |
| 1.3.5   | Depth of stabilisation                                | Depth of stabilisation   | M                                | Every 200m  | Measurement  | +15mm / -5mm from specified depth   | Daily work Log                          | Contractor   |                          |                |            |
| 1.3.6   | Compaction  | Plateau Density Test   | W                                | On first day and then 1 per 20,000m2 unless material or anvil conditions change | Draft NZTA T/24  | To establish suitability of rollers and compaction mode / pattern   | Daily work Log                          | Contractor   |                          |                |            |

| Item   | Task/Activity/Description | Detail of Activity                            | Action (Hold, Monitor, Witness) | Inspection/Test   |  | Acceptance Criteria  | Record documents | Responsibility | Comments | Checked by     |            |      |
|--------|---------------------------|---|---------------------------------|---|--|--|------------------|----------------|----------|----------------|------------|------|
|        |                           |   |                                 | Minimum Test Frequency (Lot = 1 day's production or 1,500m <sup>2</sup> )   | Inspection / Test method                               |  |                  |                |          | Engineer's Rep | Contractor | Date |
| 1.3.7  |                           | Maximum Dry Density                           | M                               | 1 per day up to 3,000 m <sup>2</sup> , 1 per 2,000m <sup>2</sup> thereafter | NZS 4402.4.1.3   | For analysis of DoC  | IANZ Report      | Contractor     |          |                |            |      |
| 1.3.8  |                           | Degree of Compaction                          | H                               | 5 per 1,000m <sup>2</sup>   | NZS 4407.4.2.1 (to 100mm and 200mm) and NZS 4407.4.2.2 | Average DoC ≥ 98%<br>Minimum DoC ≥ 95%<br>Refer NZTA T/23  | IANZ Report      | Contractor     |          |                |            |      |
| 1.3.9  | Finished Pavement         | Crossfall                                     | H                               | every 20m   | Measurement  | ± 0.5% of specified crossfall measure 2m apart   | Survey           | Contractor     |          |                |            |      |
| 1.3.10 |                           | Stabilised width                              | H                               | 1 every 20m   | Measurement  | -20mm, +100mm  | Survey           | Contractor     |          |                |            |      |
| 1.3.11 |                           | Surface Shape                                 | H                               | every 20m   | Measurement  | < 10mm using 3m straight edge  | Survey           | Contractor     |          |                |            |      |
| 1.3.12 |                           | Surface Levels                                | H                               | every 20m   | Measurement  | -5mm, +15mm  | Survey           | Contractor     |          |                |            |      |
| 1.3.13 |                           | Surface Finish                                | H                               | Per Lot   | Visual   | 1. Larger aggregate held in pace with a matrix of smaller aggregate<br>2. Smaller aggregate held in place by fine material<br>3. matrix does not displace under normal trafficking and/or sweeping | Survey           | Contractor     |          |                |            |      |
| 1.3.14 |                           | Degree of Saturation, DOS                     | H                               | 5 per lot   | Measurement  | DOS ≤ 80%  | IANZ report      | Contractor     |          |                |            |      |
| 1.4.1  | Non-conforming results    | Assessment of all test results for conformity | H                               | Each Lot  | Site Inspection  | Reporting of any non-conforming results to Designer via NCR  | NCR              | Engineer's Rep |          |                |            |      |

Client Final Inspection - the signature below verifies that this ITP has been completed in accordance with the Specifications and verifies lot compliance.

|                              |                  |             |   |               |   |
|------------------------------|------------------|-------------|---|---------------|---|
| Contractor's Rep Name: _____ | Signature: _____ | Date: _____ | H | Hold Point    | Work shall not proceed past the HP until released by the Eng. Rep.            |
| Engineer's Rep. Name: _____  | Signature: _____ | Date: _____ | W | Witness Point | An inspection which must be witnessed by the Eng. Rep.                        |
|                              |                  |             | M | Monitor Point | Intermittent monitoring of any stage of the work in progress by the Eng. Rep. |