

CTCR Pavement Construction


Hayden Brett Created Fri, 06 Sep 2024, 7:38 AM (UTC+10)

Subcontractor (If Applicable)

ITP Details:											
Clent	Construction Process	Contract Number:	Specifications	Structure / Component	Prepared By	Reviewed By:	Approved By				
Regional Roads Victoria	CTCR Pavement Construction		Vicroads Specification Section 173, 175, 205, 210, 290, 304, 702 and 720, VR Code of Practice 500.2	CTCR Pavements							
Project Location											
Lot No.											
Lot details											
Lot size/qtys											
Date		Start: -			End: -						
Legend: Legend:											

HP	Hold Point	Work shall not proceed past the HP until released by the Superintendent	IP	Inspection point	Formal Inspection to be done and recorded
IHP	SWA Internal Hold Point	Work shall not proceed past the IHP until released by SWA	TP	Test Point	Product compliance test to be undertaken and recorded/ reported

WP	Witness Point	An inspection which must be witnessed by the Superintendent	SCP	Survey conformance point	A qualified surveyor to check product/section/structure and report
AP	Approval Point	Written or verbal approval given by the Superintendent			





1. Preliminary Works

Task/Activity Description	Acceptance Criteria	Reference Documents	Method & Record of conformity	Responsibility	Signature 1	Signature 2	Comments
1.1 Delivery Vehicles	Delivery vehicles shall	Vicroads std sec 306.07		WP			
	have bodies fitted with	(a)	Inspection				
	covers of a suitable			SWA Site Supervisor/			
Frequency	material to prevent loss			Engineer			
	of moisture during						
Each Delivery Truck	transport. Vehicles used						
	for delivery of material		Record: Delivery Truck				
	to the hoppers of		Photos (2 Per Lot)				
	pavers shall have						
	bodies or discharge						
	equipment which will						
	enable the load to be						
	discharged direct into						
	the hopper without						
	spillage and in such a						
	way that segregation						
	will be minimised.						



Task/Activity Description	Acceptance Criteria	Reference Documents	Method & Record of conformity	Responsibility	Signature 1	Signature 2	Comments
1.2 Delivery Dockets	Delivery dockets shall	Vicroads std sec 306.07	Method: Visual	WP			
	show:	(b)	Inspection	SWA Site Supervisor/			
Frequency	(i) name of the supplier,			Engineer			
	and location of plant;						
Each Delivery Truck	(ii) docket number;						
	(iii) name of user;		Record: Delivery				
	(iv) project name and		Dockets Photos (2 Per				
	location (or contract number);		Lot)				
	(v) registered number or						
	fleet number of the						
	vehicle;						
	(vi) date and time of						
	loading;						
	(vii) nature and source						
	of material; (viii) empty and loaded						
	masses of the vehicle						
	(where material is						
	scheduled for						
	measurement by mass);						
	(ix) loose volume in						
	delivery vehicle.						
	delivery vehicle.						

2. Construction works



Task/Activity Description	Acceptance Criteria		Inspection method & Record of conformity	Responsibility	Signature 1	Signature 2	Comments/Attachments /Other signatures
2.1 Transverse Joints Frequency:Check prior to placing material	Material should be spread to minimize number of joints. Transverse joints shall be offset from one layer to next by not less than 2 metres	Vicroads std sec 306.08 (a, b, c)	Method: Visual Inspection Record: Signed ITP & Staging Plan	IP SWA Engineer Site Supervisor			
2.2 Longitudinal Joints Frequency: Check prior to placing material	Material should be spread to minimize number of joints. Longitudinal joints offset from one layer to next by not less than 150mm. Longitudinal joints to be located within 300mm from planned traffic lane lines or within 300 mm of the centre of a traffic lane.	Vicroads std sec 304.08 (a, d, e)	Method: Visual Inspection Record: Signed ITP & Staging Plan Photos	IP SWA Engineer Site Supervisor			
2.3 Lot Size Frequency:Check prior to placing material	A single lot shall be considered a single layer of 4000m2 or one day's production in a single layer, whichever is lesser	VcRoads Std Specs 306.09	Method: Daily Inspection Record: Signed ITP	IP SWA Engineer Site Supervisor			



Task/Activity Description	Acceptance Criteria	Reference Documents	Inspection method & Record of conformity	Responsibility	Signature 1	Signature 2	Comments/Attachments /Other signatures
2.4 Layer Thickness Frequency: Each Lot	The minimum compacted thickness shall be not less than 100mm and the maximum compacted thickness shall no more than 180mm and constructed within the tolerances specified in Clause 306.03	VcRoads Std Specs 306.03	Method: Visual Inspection Record: Signed ITP	IP SWA Engineer Site Supervisor			
2.5 Test Rolling Frequency:Test roll each layer	No visible deformation or springing in presence of Superintendent's Rep. (Cl 173) Plant to comply with requirements of Cl 173.03. Pneumatic tyred plant nominated for test rolling procedures shall have a mass of not less than 20 tonne and shall have a ground contact pressure under either the front or rear wheels of not less than 450 kPa per tyre.	173.03 (ii) Table 306.091	Method: Visual Inspection Record: Signed ITP	IHP SWA Engineer Site Supervisor AP RRV Superintendent			



Task/Activity Description	Acceptance Criteria	Reference Documents	Inspection method & Record of conformity	Responsibility	Signature 1	Signature 2	Comments/Attachments /Other signatures
2.6 Max. Working Time	The cementitious treated subbase material shall be placed, trimmed to level and	VcRoads Std Specs 306.09	Method: Visual Inspection	IHP SWA Engineer			
Frequency:Test roll each layer	fully compacted within the maximum allowable working time specified in Table 306.091 depending on the binder type and the time of year the subbase is		Record: Signed ITP	Site Supervisor			
	Deing placed. The ISBN Nation Reseals thereby these the things for common constitution broken. Generally and the Common						



Task/Activity Description	Acceptance Criteria	Reference Documents	Inspection method & Record of conformity	Responsibility	Signature 1	Signature 2	Comments/Attachments /Other signatures
	Acceptance Criteria The minimum compacted thickness shall be not less than 100 mm and the maximum compacted thickness shall be no more than 180 mm and constructed within the tolerances specified in Clause 306.03. (a) Pavement Design Modulus of 500 MPa or where no Pavement Design Modulus is Specified	Reference Documents VcRoads Std Specs 306.11		Responsibility IP SWA Engineer Site Supervisor	Signature 1	Signature 2	
	The surface of each compacted layer shall be kept moist for a period of seven days unless covered at an earlier stage with the succeeding layer or with an approved curing membrane. Construction or other traffic shall not use a compacted layer within 24 hours of placement without the approval of the Superintendent. The subbase shall be kept in good order and condition and free from contamination.						



3. Testing Requirements

Task/Activity Description	Acceptance Criteria	Reference Documents	Inspection method & Record of conformity	Responsibility	Signature 1	Signature 2	Others
3.1 Determine Testing Scale & Initial testing frequency Frequency:Prior to testing	Table 306.031 from VicRoads Section 306 nominates the level of testing required for acceptance of Surface Level Measurement. Scale B - Initially test every lot as per Table 815.141 except where the most recent ten successive test results have met the specified requirements then the testing may be halved.	Vicroads std sec 306.031 815.14 & Table 815.141	Method: Lot Register Record: Signed ITP	TP SWA Engineer			
3.2 Compaction Testing Frequency: Each lot as required	The cementitious treated subbase material shall be placed, trimmed to level and fully compacted within the maximum allowable working time specified in Table 306.091 depending on the binder type and the time of year the subbase is being placed (May – Sep). For scale A requirements, the number of tests per lot shall be six. The lot will be accepted if the mean density ratio for the lot is not less than 96.0%.		Method: Compaction Testing External Record: Signed ITP & Test Reports	TP SWA Engineer AP RRV Superintendent			



Task/Activity Description	Acceptance Criteria	Reference Documents	Inspection method & Record of conformity	Responsibility	Signature 1	Signature 2	Others
3.3 UCS Frequency:Each lot as required	Assessment of the UCS during production shall be on a 'rolling average' basis where the average of the most recent three UCS test results shall not be less than the minimum value specified in Table 821.081. (For rapid/slow setting cement the min UCS is 5 MPa for pavement >500 or <3500.)		Method: Test Results Record: Signed ITP & Test Reports	TP SWA Engineer			
3.4 Atterberg Limits Frequency:Each lot as required	The crushed concrete prior to the addition of cementitious binder shall comply with the requirements of Table 821.041 Liquid Limit % - 35 Plasticity Index (max) - 10 LA Value (max) - 40	VcRoads Std Specs Table 821.041	Method: Test Results Record: Signed ITP & Test Reports	TP SWA Engineer			
3.5 Moisture Content Frequency: Each lot as required	The moisture content of the material at the time of spreading and compaction, expressed as a percentage by mass, shall be within plus 0.5% and minus 1.0% from the Modified optimum moisture content.	VcRoads Std Specs 306.05	Method: Test Results Record: Signed ITP & Test Reports	TP SWA Engineer			



Task/Activity Description	Acceptance Criteria	Reference Documents	Inspection method & Record of conformity	Responsibility	Signature 1	Signature 2	Others
3.6 Cement Content Frequency: Each lot as required	After mixing, the cementitious binder content of the mixture, expressed as a percentage by mass of the dry crushed rock, shall be within +/- 0.3% of the Design Cementitious Binder Content.	VcRoads Std Specs 815.10	Method: Test Results Record: Signed ITP & Test Reports	TP SWA Engineer			
3.7 Grading Frequency:Each lot as required	The product shall not extend outside the specified grading limits as per table 821.071	VcRoads Std Specs Table 821.071	Method: Test Results Record: Signed ITP & Test Reports	TP SWA Engineer			



Task/Activity Description	Acceptance Criteria	Reference Documents	Inspection method & Record of conformity	Responsibility	Signature 1	Signature 2	Others
3.8 Survey	Layer to be finished to a	VcRoads Std Specs	Method: Survey Report	SCP			
Conformance	smooth and uniform	306.03 & Table 306.031,					
	surface and after compaction shall	306.032		SWA Engineer			
Frequency:Each lot as	conform within the			AP			
required	following limits:						
	Shape: no point		Record: Signed ITP &	RRV Superintendent			
	deviation > 8mm from		Survey Reports				
	3m straight edge in any						
	direction						
	Surface level						
	tolerances: Range x = +6, -12mm						
	Max S = 13 mm						
	Min number of						
	measurement levels for						
	Scale B requirements is						
	40 measurements per						
	lot						

-inal inspection Notes	
------------------------	--

Photo and video		
Project Team signature	Not signed yet.	
Photo and video		
Final Inspection Notes		
Client Signature	Not signed yet.	